

# CR LAURENCE CO., INC. TEST REPORT

**SCOPE OF WORK**

AIR / WATER / STRUCTURAL TESTING ON 550 T / 550 AT.  
SIDE HINGED DOOR (SINGLE – OUTSWING)

**REPORT NUMBER**

I8133.01-303-47 R1

**TEST DATE**

08/22/18

**ISSUE DATE**

08/23/18

**REVISION DATE**

08/30/18

**RECORD RETENTION END DATE**

08/22/22

**PAGES**


12

**DOCUMENT CONTROL NUMBER**

ATI 00479 (07/24/17)

RT-R-AMER-Test-2805

© 2017 INTERTEK



## TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I8133.01-303-47 R1

Date: 08/23/18

### REPORT ISSUED TO

**CR LAURENCE CO., INC.**

2503 East Vernon Avenue  
Los Angeles, California 90058

### SECTION 1

#### SCOPE

Intertek Building & Construction (B&C) was contracted by CR Laurence Co., Inc., 2503 East Vernon Avenue, Los Angeles, California to perform testing in accordance with ASTM E283, *Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*, ASTM E330, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*, ASTM E331, *Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*, on their 550 T / 550 AT, Side Hinged Door (Single – Outswing). Results obtained are tested values and were secured by using the designated test methods. Testing was conducted at CR Laurence Co., Inc. test facility in Los Angeles, California.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

### SECTION 2

#### SUMMARY OF TEST RESULTS

| TITLE                                      | RESULTS  |
|--|--|
| Design Pressure                            | ±960 Pa (±20.05 psf)                               |
| Air Infiltration                           | 0.2 L/s/m <sup>2</sup> (0.04 cfm/ft <sup>2</sup> ) |
| Water Penetration Resistance Test Pressure | 0 Pa (0.00 psf)                                    |
| Uniform Load Structural Test Pressure      | ±1440 Pa (±30.08 psf)                              |

For INTERTEK B&C:

|                      |                 |
|----------------------|-----------------|
| <b>COMPLETED BY:</b> | Charles Presley |
| <b>TITLE:</b>        | Technician II   |
| <b>SIGNATURE:</b>    |                 |
| <b>DATE:</b>         | 08/24/18        |

jsh:ab

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

## TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I8133.01-303-47 R1

Date: 08/23/18

### SECTION 3

#### TEST METHOD(S)

The specimens were evaluated in accordance with the following:

**AAMA 205-15**, *In-Plant Testing Guidelines for Manufacturers and Independent Laboratories*

**ASTM E283-04(2012)**, *Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*

**ASTM E330/E330M-14**, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

**ASTM E331-00(2016)**, *Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*

### SECTION 4

#### MATERIAL SOURCE/INSTALLATION

Test specimen was provided by the client. Representative samples of the test specimen were retained by the customer.

The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a 3/8" shim space at head and jambs and flush install at threshold. The interior and exterior perimeter of the door was sealed with silicone sealant. Installation of the tested product was performed by the client.

| LOCATION               | ANCHOR DESCRIPTION                 | ANCHOR LOCATION                             |
|------------------------|------------------------------------|---|
| Through threshold      | #10 x 2" flat head wood screw      | 3" from each end and 12" on center spacing. |
| Through head and jambs | #10 x 3-1/4" flat head wood screws | 3" from each end and 12" on center spacing. |

### SECTION 5

#### EQUIPMENT

Calibration of test equipment was performed by Intertek B&C in accordance with AAMA 205-01 "In-Plant Testing Guidelines for Manufacturers and Independent Laboratories"

## TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I8133.01-303-47 R1

Date: 08/23/18

### SECTION 6

#### LIST OF OFFICIAL OBSERVERS

| NAME             | COMPANY               |
|------------------|-----------------------|
| Garrett Osterode | CR Laurence Co., Inc. |
| Charles Presley  | Intertek B&C          |

### SECTION 7

#### TEST SPECIMEN DESCRIPTION

**Product Type:** Side Hinged Door (Single – Outswing)

**Series/Model:** 550 T / 550 AT

#### Product Size(s):

| OVERALL AREA:                              | WIDTH       |        | HEIGHT      |         |
|--|-------------|--------|-------------|---------|
|  | millimeters | inches | millimeters | inches  |
| 3.3 m <sup>2</sup> (35.4 ft <sup>2</sup> ) |             |        |             |         |
| Overall Size                               | 1321        | 52     | 2489        | 98      |
| Leaf                                       | 1219        | 48     | 2419        | 95-3/16 |

#### Frame Construction:

| FRAME MEMBER   | MATERIAL     | DESCRIPTION  |
|----------------|--------------|--|
| Head and jambs | Aluminum     | Thermally broken frame extrusion, Part No. IT442, see attached drawings Section 10.  |
| Sill           | Aluminum     | Thermally broken threshold extrusion, Part No. TT245, see attached drawings Section 10.  |
| Head and jambs | Aluminum     | Pocket filler extrusion, Part No. PV100, press fit into back side of frame extrusion, see attached drawings Section 10.                  |
| Head and jambs | Aluminum     | Thermally broken door stop extrusion, Part No. DS051, press fit into interior side of frame extrusion, see attached drawings Section 10. |
|                | JOINERY TYPE | DETAIL   |
| All Corners    | Flush        | Secured at head corners with shear clip (Part No. IP442) fastened with ST240 Frame Assembly screws.                                      |

## TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I8133.01-303-47 R1

Date: 08/23/18

### Leaf Construction (550 T):

| LEAF MEMBER | MATERIAL     | DESCRIPTION  |
|-------------|--------------|--|
| Top rail    | Aluminum     | Thermally broken leaf extrusion, Part No. WT201, see attached drawings Section 10. |
| Bottom rail | Aluminum     | Thermally broken leaf extrusion, Part No. JT650, see attached drawings Section 10. |
| Hinge stile | Aluminum     | Thermally broken leaf extrusion, Part No. WT550, see attached drawings Section 10. |
| Lock stile  | Aluminum     | Thermally broken leaf extrusion, Part No. WT400, see attached drawings Section 10. |
|             | JOINERY TYPE | DETAIL   |
| All Corners | Flush        | Secured through stiles with #8 x 1" FH SMS, four per corner.                       |

### Leaf Construction (550 AT):

| LEAF MEMBER | MATERIAL     | DESCRIPTION   |
|-------------|--------------|---|
| Top rail    | Aluminum     | Thermally broken leaf extrusion, foam filled extrusion, Part No. WT201, see attached drawings Section 10. |
| Bottom rail | Aluminum     | Thermally broken leaf extrusion, foam filled extrusion, Part No. JT650, see attached drawings Section 10. |
| Hinge stile | Aluminum     | Thermally broken leaf extrusion, foam filled extrusion, Part No. WT550, see attached drawings Section 10. |
| Lock stile  | Aluminum     | Thermally broken leaf extrusion, Part No. WT400, see attached drawings Section 10.                        |
|             | JOINERY TYPE | DETAIL  |
| All Corners | Flush        | Secured through stiles with #8 x 1" FH SMS, four per corner.  |

**Reinforcement:** *No reinforcement was utilized.*

## TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I8133.01-303-47 R1

Date: 08/23/18

### Weatherstripping:

| DESCRIPTION                         | QUANTITY | LOCATION  |
|-------------------------------------|----------|---|
| Bulb seal, Part No. WH349           | 1 row    | Channel inserted into glass stop at head and jambs.           |
| Door sweep assembly, Part No. BW200 | 1        | Attached to interior face of bottom rail full span of member. |

**Glazing:** *No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.*

| GLASS TYPE | SPACER TYPE                        | INTERIOR LITE       | EXTERIOR LITE       | GLAZING METHOD   |
|------------|------------------------------------|---------------------|---------------------|--|
| 1" IG      | Aluminum Spacer – Dual Seal (A1-D) | 1/4" Clear Tempered | 1/4" Clear Tempered | Exterior dry glazed with setting blocks at base (Part No. SB245). Sealed at interior with EPDM gasket (Part No. NP252), at exterior with EPDM wedge gasket (Part No. NP225), and glass stop (Part No. HE751) at top and bottom rail. |

| LOCATION | QUANTITY | DAYLIGHT OPENING |                     | GLASS BITE |
|----------|----------|------------------|---------------------|------------|
|          |          | millimeters      | inches              |            |
| Leaf     | 1        | 935 x 2057       | 36-13/16 x 81-15/16 | 1/2"       |

**Drainage:** *No drainage was utilized.*

### Hardware:

| DESCRIPTION  | QUANTITY | LOCATION   |
|--|----------|--|
| Hook bolt lock and cylinder, Part Nos. DH129 and DH004 | 1        | Through lock stile 34-1/4" from sill.            |
| Stainless steel butt hinge, Part No. BB55NR            | 3        | Located 11-1/2" from sill and 38-1/2" on center. |

**Screen Construction:** *No screen was utilized.*

**TEST REPORT FOR CR LAURENCE CO., INC.**

Report No.: I8133.01-303-47 R1

Date: 08/23/18

**SECTION 8**

**TEST RESULTS**

The temperature during testing was 22°C (72°F). The results are tabulated as follows:

| TITLE OF TEST   | RESULTS   | NOTE |
|---|---|------|
| <b>Air Leakage,</b><br>Infiltration per ASTM E283<br>at 75 Pa (1.57 psf)  | 0.2 L/s/m <sup>2</sup><br>(0.04 cfm/ft <sup>2</sup> ) |      |
| <b>Water Penetration,</b><br>per ASTM E331<br>at 0 Pa (0.00 psf)  | Pass  | 1    |
| <b>Uniform Load Deflection,</b><br>per ASTM E330<br>Deflections taken at lock stile<br>+960 Pa (+20.05 psf)<br>-960 Pa (-20.05 psf)     | 0.3 mm (0.01")<br>0.0 mm (0.00")                      | 2, 3 |
| <b>Uniform Load Structural,</b><br>per ASTM E330<br>Permanent set taken at lock stile<br>+1440 Pa (+30.08 psf)<br>-1440 Pa (-30.08 psf) | 0.0 mm (0.00")<br>2.0 mm (0.08")                      | 2, 3 |

**General Note:** All testing was performed in accordance with the referenced standard(s).

*Note 1:* Water penetration testing performed in accordance with Limited Water designation.

*Note 2:* Loads were held for 10 seconds.

*Note 3:* Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.

## TEST REPORT FOR CR LAURENCE CO., INC.


Report No.: I8133.01-303-47 R1

Date: 08/23/18

### SECTION 9

#### LOCATION OF AIR SEAL

The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.





Total Quality. Assured.

25800 Commercentre Drive  
Lake Forest, California 92630

Telephone: 949-460-9600  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)


**TEST REPORT FOR CR LAURENCE CO., INC.**

Report No.: I8133.01-303-47 R1

Date: 08/23/18

**SECTION 10**  
**DRAWINGS**


The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein.



WIDE STILE SERIES 550-T & 550-AT ELEVATION  
 (SINGLE DOOR @ UP / OVER FRAME)  $3/4" = 1'-0"$

| ITEM | PT. NO. | PART DESCRIPTION  |
|------|---------|---|
| C1   | IT442   | FRAME/HEAD EXTRUSION                                    |
| C2   | PV100   | POCKET FILLER   |
| C3   | DS051   | DOOR STOP   |
| C4   | IP442   | SHEAR CLIP (W/ ST254 SCREWS)                            |
| C5   | WT201   | DOOR FRAME-TOP RAIL                                     |
| C6   | JT650   | DOOR FRAME-BOTTOM RAIL                                  |
| C7   | WT550   | DOOR FRAME-HINGE STILE                                  |
| C8   | WT400   | DOOR FRAME-LOCK STILE                                   |
| C9   | HE751   | GLAZING STOP  |
| C10  | TT245   | THRESHOLD   |
| G1   |         | 1" INSUL GLASS-1/4" TEMP. - 1/2" AIR SPACE - 1/4" TEMP. |
| G2   | NP225   | EDPM-TOP LOAD GASKET                                    |
| G3   | NP252   | EDPM-SETTING GASKET                                     |
| G4   | SB245   | SETTING BLOCK   |
| H1   | ST240   | FRAME ASSEMBLY SCREWS                                   |
| H2   | -----   | #10 X 3-1/4" FH WOOD SCREWS                             |
| H3   | BB55NR  | STAINLESS STEEL BUTT HINGES                             |
| H4   | DH129   | HOOK BOLT LOCK  |
| H5   | DH004   | CYLINDER  |
| H6   | -----   | #10 X 2" FH WOOD SCREWS                                 |
| W1   | WH349   | BULB SEAL   |
| W2   | BW200   | DOOR SWEEP  |
| W3   | DC795   | DOW CORNING 795-BUILDING SEALANT                        |
| W4   | EF38C   | CLOSED CELL BACKER ROD                                  |

REVISIONS




**CRL**  
 C.R. LAURENCE CO.  
 ARCHITECTURAL PRODUCTS  
 2100 E. 38TH Street, Los Angeles, CA 90058  
 www.crlaurence.com

Job Name: **SERIES 550-T & 550-AT  
 WIDE STILE - 48" X 96"  
 ADVANCED THERMAL DOOR**


Glazing Contractor:

|             |           |
|-------------|-----------|
| DATE:       | 4.4.2018  |
| DRAWN BY:   | GDO       |
| CHECKED BY: |           |
| SCALE:      | AS SHOWN  |
| JOB #:      | PTC754301 |


SHT 1 OF 2




① SECTION DETAIL @ DOOR JAMB  
SCALE: FULL SIZE



② SECTION DETAIL @ DOOR JAMB  
SCALE: FULL SIZE



③ SECTION DETAIL @ 6" TOP RAIL  
SCALE: FULL SIZE



④ SECTION DETAIL @ 7 1/4" DOOR SILL  
SCALE: FULL SIZE

REVISIONS



**CRL**  
C.R. LAURENCE CO.  
ARCHITECTURAL PRODUCTS  
2100 E. 38TH Street, Los Angeles, CA 90058  
www.crlaurence.com

SERIES 550-T & 550-AT  
WIDE STILE - 48" X 96"  
ADVANCED THERMAL DOOR

Job Name:

Glazing Contractor:

DATE: 4.4.2018  
DRAWN BY: GDO  
CHECKED BY:  
SCALE: AS SHOWN  
JOB #: PTC754-301



Total Quality. Assured.

25800 Commercentre Drive  
Lake Forest, California 92630

Telephone: 949-460-9600  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

**TEST REPORT FOR CR LAURENCE CO., INC.**

Report No.: I8133.01-303-47 R1

Date: 08/23/18

**SECTION 11**

**REVISION LOG**

| REVISION # | DATE     | PAGES | REVISION                                  |
|------------|----------|-------|---|
| 0          | 08/23/18 | N/A   | Original Report Issue                     |
| 1          | 08/30/18 | 7     | Correct test results notation references. |