

CR LAURENCE CO., INC.

TEST REPORT

SCOPE OF WORK

AAMA/WDMA/CSA 101/I.S.2/A440-17 TESTING ON PALISADES S90 BI-FOLD DOOR

REPORT NUMBER

M2744.01-303-47-R2

TEST DATE(S)

04/15/21 - 04/19/21

ISSUE DATE

04/27/21

REVISION DATE

06/16/21

RECORD RETENTION END DATE

04/19/25

PAGES


16

DOCUMENT CONTROL NUMBER

ATI 00438 (07/24/17)

RT-R-AMER-Test-2804

© 2017 INTERTEK



TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

REPORT ISSUED TO

CR LAURENCE CO., INC.

2503 E. Vernon Avenue
Los Angeles, California 90058

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by CR Laurence Co., Inc. to perform testing in accordance with AAMA/WDMA/CSA 101/I.S.2/A440-17, *NAFS 2017 - North American Fenestration Standard/Specification for Windows, Doors, and Skylights*, on their Palisades S90, Bi-Fold Door System. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at CR Laurence Co., Inc. test facility in Los Angeles, California. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

TITLE	RESULTS
AAMA/WDMA/CSA 101/I.S.2/A440-17	Class CW – PG30: Size Tested 2794 x 3048 mm (110 x 120 in.) – Type FLD
Design Pressure	±1440 Pa (±30.08 psf)
Air Infiltration	1.3 L/s/m ² (0.25 cfm/ft ²)
Water Penetration Resistance Test Pressure	290 Pa (6.06 psf)

For INTERTEK B&C:

COMPLETED BY:	Aaron Baker
TITLE:	Technician Team Lead
SIGNATURE:	
DATE:	06/16/21

jsh:ab

REVIEWED BY:	Jarod Hardman
TITLE:	Operations Manager
SIGNATURE:	
DATE:	06/16/21

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

SECTION 3

TEST METHOD(S)

The specimens were evaluated in accordance with the following:

AAMA/WDMA/CSA 101/I.S.2/A440-17, *NAFS 2017 - North American Fenestration Standard/Specification for Windows, Doors, and Skylights*

AAMA 205-15, *In-Plant Testing Guidelines for Manufacturers and Independent Laboratories*

AAMA 1304-02, *Voluntary Specification for Forced Entry Resistance of Side-Hinged Door Systems*

ASTM E283-04(2012), *Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*

ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

ASTM E547-00(2016), *Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Cyclic Static Air Pressure Difference*

ASTM E987-88(2009), *Standard Test Methods for Deglazing Force of Fenestration Products*

ASTM F842-14, *Standard Test Methods for Measuring the Forced Entry Resistance of Sliding Door Assemblies, Excluding Glazing Impact*

AAMA 920-11, *Specification for Operating Cycle Performance of Side-Hinged Exterior Door Systems*

SECTION 4

MATERIAL SOURCE/INSTALLATION

Test specimen was provided by the client. Representative samples of the test specimen(s) will be retained by Intertek B&C for a minimum of four years from the test completion date.

The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a 1/4" shim space. The exterior perimeter of the door was sealed interior and exterior with structural silicone sealant. Installation of the tested product was performed by the client.

LOCATION	ANCHOR DESCRIPTION	ANCHOR LOCATION
Through frame	#10 x 3" flat head wood screw	Two fasteners per location through head, and jambs.
Through frame	#10 x 2" flat head screws	Two fasteners per location through sill.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

SECTION 5 EQUIPMENT

Calibration of test equipment was performed by Intertek B&C in accordance with AAMA 205-01 "In-Plant Testing Guidelines for Manufacturers and Independent Laboratories"

SECTION 6 LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Garrett Osterode	CR Laurence Co., Inc.
Aaron Baker	Intertek B&C

SECTION 7 TEST SPECIMEN DESCRIPTION

Product Type: Bi-Fold Door
Series/Model: Palisades S90

Product Size(s):

OVERALL AREA:	WIDTH		HEIGHT	
8.5 m ² (91.7ft ²)	millimeters	inches	millimeters	inches
Overall Size	2794	110	3048	120

Frame Construction:

FRAME MEMBER	MATERIAL	DESCRIPTION
Head	Aluminum	S85 Top Track, thermally broken extrusion, Part No. S85HEADDU, see attached Drawings Section 11.
Sill	Aluminum	S85 Sill Track, thermally broken extrusion, Part No. S850SS1LLDU, see attached Drawings Section 11.
Jambs	Aluminum	Lateral Frame, thermally broken extrusion, Part No. S85HJAMBDU, see attached Drawings Section 11.
	JOINERY TYPE	DETAIL
All Corners	Coped	Secured through end of frame.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

Leaf Construction:

LEAF MEMBER	MATERIAL	DESCRIPTION
Stiles and rails	Aluminum	Panel, thermally broken extrusion, Part No. S85PANELDU, see attached Drawings Section 11.
Side hinged lock stile	Aluminum	S85 Jamb Extender, thermally broken extrusion, Part No. S85JAMBEXT, see attached Drawings Section 11.
Bi-fold lock stile	Aluminum	Post w/ Roller, thermally broken extrusion, press fit to panel stile, Part No. S85EVEN_ROLLER, see attached Drawings Section 11.
Bi-fold hinge stile	Aluminum	Intermediate Post Assembly, thermally broken extrusion, secured to panel stiles with hinges, Part No. S85POST, see attached Drawings Section 11.
	JOINERY TYPE	DETAIL
All Corners	Coped	Secured through frame.

Reinforcement: *No reinforcement was utilized.*
Weatherstripping:

DESCRIPTION	QUANTITY	LOCATION
Flock lined single bulb gasket, Part No. MDAC350208	2 rows	Exterior leg of sill frame, see attached Drawings Section 11.
Flock lined single bulb gasket, Part No. MDAC350208	1 row	Exterior leg of head frame, see attached Drawings Section 11.
S55 Pre-Chamber Gasket, Part No. MDAC350203	1 row	Exterior leg of jamb frame, see attached Drawings Section 11.
Gasket Reinforced Post, Part No. S85GRP	1 row	Press fit onto jambs and intermediate posts, see attached Drawings Section 11.
Gasket – Low Friction Slip, Part No. S85GDR	2 rows	Kerf inserted at interior and exterior legs of stiles, see attached Drawings Section 11.
Gasket – Low Friction Slip, Part No. S85GDR	1 row	Kerf inserted at exterior leg of rails, see attached Drawings Section 11.
Gasket – Horiz Door Panel, Part No. S85GDRH	1 row	Channel inserted into interior leg of rails, see attached Drawings Section 11.
Pile, part No. 30018745BKWP	1 row	Channel inserted at head of frame, see attached Drawings Section 11.
Bulb Gasket, Part No. WH342001500.	1 row	Channel inserted into side hinged lock stile, see attached Drawings Section 11.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

Glazing: *No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.*

GLASS TYPE	SPACER TYPE	INTERIOR LITE	EXTERIOR LITE	GLAZING METHOD
1" IG	Aluminum Spacer – Dual Seal (A1-D)	1/4" clear tempered	1/4" clear tempered	Exterior set dry glazed with bulb gasket (Part No. WH342001500) at interior and wedge gasket (Part No. WH416) at exterior. Glass stop at top and bottom rails (Part No. S85GLV), glass stop on stiles (Part No. S85GLHVDU).

LOCATION	QUANTITY	DAYLIGHT OPENING		GLASS BITE
		millimeters	inches	
Leaf	3	779 x 2886	30-11/16 x 113-5/8	5/8"

Drainage:

DRAINAGE METHOD	SIZE	QUANTITY	LOCATION
Weep slots	1-3/4" wide by 3/4" high	6	Through the face of the sill.

Hardware:

DESCRIPTION	QUANTITY	LOCATION
End dams, Part No. S85EDBRL / S85EDBRR	2	Located at sill on both ends of system, see attached Drawings Section 11.
Concealed hinge, Part No. S85H1NGE	25	Located at stiles of each panel pivot, see attached Drawings Section 11.
Catch Back Plate, Part No. S85CATCHBP	2	Located at bi-fold intermediate post, see attached Drawings Section 11.
Top/Bottom Bolt Guide, Part No. S85BOLTGUIDE	2	Located at bi-fold intermediate post, see attached Drawings Section 11.
SS Catch Bolt, Part No. S85CATCHBOLT	2	Located at bi-fold intermediate post, see attached Drawings Section 11.
S85 CYLINDERKIT 80 Lock Assembly, Part Nos. TH7824238 / TH7864219 / TH7974227	1	Located on lock stile of side hinged door 37-3/4" from sill, see attached Drawings Section 11.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

DESCRIPTION	QUANTITY	LOCATION
S85 CYLINDERKIT 80 Strike Assembly, Part Nos. TH70199 / TH70299 / TH70399	1	Located opposite lock stile of side hinged door 37-3/4" from sill, see attached Drawings Section 11.
Roller, Part No. S85BROLLER	1	Located on bottom of intermediate post, see attached Drawings Section 11.
Top Guide, Part No. S85TGU1DE	1	Attached to the top of panel assemblies, see attached Drawings Section 11.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

SECTION 8
TEST RESULTS

The temperature during testing was 16°C (60°F). The results are tabulated as follows:

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	1.3 L/s/m ² (0.25 cfm/ft ²)	1.5 L/s/m ² (0.3 cfm/ft ²) max.	1, 2
Water Penetration, per ASTM E547 at 290 Pa (6.06 psf)	Pass	No leakage	
Uniform Load Deflection, per ASTM E330 Deflections taken at lock stile +1440 Pa (+30.08 psf) -1440 Pa (-30.08 psf)	11.7 mm (0.46") 15.5 mm (0.61")	17.0 mm (0.67") max. 17.0 mm (0.67") max.	3, 4, 5, 6
Uniform Load Structural, per ASTM E330 Permanent set taken at lock stile +2160 Pa (+45.11 psf) -2160 Pa (-45.11 psf)	1.8 mm (0.07") 1.5 mm (0.06")	8.9 mm (0.35") max. 8.9 mm (0.35") max.	4, 5, 6
Forced Entry Resistance, per ASTM F842, Type: B - Grade: 10	Pass	No entry	
Forced Entry Resistance, per AAMA 1304	Pass	No entry	
Deglazing, per ASTM E987 Operating direction, 320 N (70 lbf) Remaining direction, 230 N (50 lbf)	Pass Pass	Meets as stated Meets as stated	
Operation/Cycling Performance, per AAMA 920 # 250,000 cycles	Pass	Meets as stated	7

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

Note 1: The tested specimen meets (or exceeds) the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air leakage resistance.

Note 2: Test Date 04/15/21 / Time: 08:00 AM

Note 3: The client opted to start at a pressure higher than the minimum required. Test results are reported under Optional Performance.

Note 4: The deflections reported are not limited by AAMA/WDMA/CSA 101/I.S.2/A440 for this product designation. The deflection data is recorded in this report for special code compliance and information only.

Note 5: Loads were held for 10 seconds.

Note 6: Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.

Note 7: At the conclusion of the test, there were no signs of damage to the door panel, frame, construction, fasteners, glazing, weatherstripping, or system assembly.

SECTION 9

ALTERATIONS

No alterations were required.

TEST REPORT FOR CR LAURENCE CO., INC.


Report No.: M2744.01-303-47-r2

Date: 04/27/21

SECTION 10

LOCATION OF AIR SEAL

The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.





Total Quality. Assured.

25800 Commercentre Drive
Lake Forest, California 92630

Telephone: 949-460-9600
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21


SECTION 11

DRAWINGS

The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.



$$1'' = 1' - 0''$$

1.0




① JAMB @ DOOR DETAIL

ARCH REF: NONE 1'-0"=1'-0"




② DOOR @ POST W/ROLLER DETAIL

ARCH REF: NONE 1'-0"=1'-0"



③ MID PANEL POST DETAIL

ARCH REF: NONE 1'-0"=1'-0"



④ JAMB @ STACK SIDE DETAIL


ARCH REF: NONE 1'-0"=1'-0"

Rev #	Date	Drawn by
0		
1		
2		
3		
4		
5		
6		

CRH ALUMINUM
A CRH COMPANY
2503 E. Vernon Avenue, Los Angeles, CA 90038-1877
PH (800) 421-1414 FAX (800) 367-7261 www.cchr.com

PALISADES S90 BI-FOLD SOOR SYSTEM


Drawn By :	GDO
Checked By :	
Date :	3.15.2021
Scale :	AS SHOWN
Job # :	MS
ESO # :	
Sheet No.	2.0



① JAMB @ DOOR DETAIL (OPEN)

ARCH REF: NONE


1'-0"=1'-0"



② DOOR @ POST W/ROLLER DETAIL (OPEN)

ARCH REF: NONE


1'-0"=1'-0"



③ MID PANEL POST DETAIL (OPEN)

ARCH REF: NONE

1'-0"=1'-0"



④ JAMB @ STACK SIDE DETAIL (OPEN)

ARCH REF: NONE

1'-0"=1'-0"

CRH
ALUMINUM
A CRH COMPANY

2503 E. Vernon Avenue, Los Angeles, CA 90008-1877
PH (800) 421-1414 FAX (800) 367-7261 www.cohere.com


PALISADES S90 BI-FOLD SOOR SYSTEM

Drawn By : GDO
Checked By :
Date : 3.15.2021
Scale : AS SHOWN
Job # : MS
ESO # :

Sheet No.

2.1


Rev #	Date	Drawn by
0		
1		
2		
3		
4		
5		
6		



1 HEAD DETAIL

ARCH REF: NONE

1'-0"=1'-0"



2 SILL DETAIL

ARCH REF: NONE

1'-0"=1'-0"

ITEM		PART NO.	DESCRIPTION
F1	✓	S85HJAMBDU	LATERAL FRAME; DARK BRONZE ANODIZE
F2	✓	S85PANELDU	PANEL (INSWING & OUTSWING)
F3	✓	S85GLHVDU	S85 GLAZING STOP W/PULL HANDLE
F4	✓	S85PANELDU	PANEL EXTRUSION (IN/OUTSWING)
F5	✓	S85EVEN_ROLLER	POST w/roller
F6	✓	S85POST	INTERMEDIATE POST ASSEMBLY
F7	✓	S85GLV	S85 GLAZING STOP
F8	✓	S850SS1LLDU	S85 SILL TRACK
F9	✓	S85HEADDU	S85 TOP TRACK
F10	✓	S85JAMBEXT	S85 JAMB EXTENDER
G1	✓	1" I.G.	INSULATED GLASS
H1	✓	S85H1NGE	CONCEALED HINGE
H1.1	✓	S85CATCHBP	CATCH; BACK PLATE
H1.2	✓	S85BOLTGUIDE	TOB/BOTTOM BOLT GUIDE
H2	✓	S85EDBRL/S85EDBRR	END DAMS
H3	✓	#10X3FHWS	FLAT HEAD WOOD SCREW
H3.1	✓	#10X2FH	FLAT HEAD WOOD SCREW
H4	✓	S85BROLLER	ROLLER
H4.1	✓	S85TGU1DE	S85 TOP GUIDE
H5	✓	MDAC3501109	S55/S55R-S80/S80R KEY CYLINDER
H7	✓	MDHANDLES	S55/S55R-S80/S80R SQ/ HANDLES
H8	✓	MDPC052	S55/S55R DBL STRIKE
H9	✓	S85CATCHBOLT	SS CATCH BOLT
S1	✓	DC795BL	DOW CORNING 795
S2	✓	38ROD	BACKER ROD
W1	✓	S85GDR	GASKET - LOW FRICTION SLIP
W2	✓	WH342001500	BULB GASKT
W3	✓	MDAC350208	FLOCK-LINED DOUBLE BULB GASKET
W4	✓	S85GRP	GASKET-REINFORCEMENT POST
W5	✓	WH416	WEDGE GASKET
W6	✓	S85GDRH	GASKET-HORIZ. DOOR RAIL
W7	✓	MDAC350203	S55/S55R-S80/S80R PRE-CHAMBER GSKT
W8	✓	S85GDRS	S85 DOOR RAIL GASKET
W9	✓	MDAC350208	FLOCK LINED SINGLE BULB GASKET
W10	✓	S85GDRS	
W11	✓	30018745BKWP	

Rev #	Date	Drawn by
0		
1		
2		
3		
4		
5		
6		



PALISADES S90 BI-FOLD SOOR SYSTEM

Drawn By	: GDO
Checked By	:
Date	: 3.15.2021
Scale	: AS AHOWN
Job #	: MS
ESO #	:

Sheet No.

3.0



Total Quality. Assured.

25800 Commercentre Drive
Lake Forest, California 92630

Telephone: 949-460-9600
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: M2744.01-303-47-r2

Date: 04/27/21

SECTION 12

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	04/27/21	N/A	Original Report Issue
1	04/29/21	7	Correct pass/fail criteria deflection value.
2	06/16/21	3,8,9	Test Methods, Results, Notes