


Building Glass Railing Systems Safer, Strong, with Brilliant Transparency

OFFICIAL TEST REPORT

For CRL's Laminated Glass Rail System

For CRL's 1" (25.52) Laminated Glass Railing System Specifications: ASTM-E330, ASTM-E1996 (Impacts Only) and ANSI Z-97.1



Report Date: 6/22/2010 Completion Date: 5/19/2010

Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143


OFFICIAL TEST REPORT

MATERIAL CHARACTERISTICS				
Members	Material**	Part Number**	Joint Type	
Cap Hand Rail:	stainless steel	** Part Number CRL LR20	none	
Glass Shoe Base:	6063-T52	** Part Number L25S10D	none	

	Glazing		
Glazing Location	Glazing Material	Glazing Compound	Compound Color
All three lites of glass	*25.5 mm nominal laminated glass composed of *(2) 1/2" Temp Glass	None	None
Interlaying Film: 0.06	0" **DuPont SentryGlas Plus	Laminator: Oldcastle	
Gl	mple is pocket glazed system using a azed at bottom with CRL taper lock cl aped setting block and taper locking c cated 6" from each end and remaining	amping system which consis lamps between glass and alur	ts of a " L "
Daylight Opening	60" by 36" high		

	Product Markings	
None		

	Additional Informatio	n
Quantity and Type	Location	Method of Attachment
One part number **CRL LR21PV vinyl gasket	between glass and hand rail	none
One part number ** CRL LTLSB setting block	between shoe base and glass	none
One part number ** CRL LTLGSO taper locking clamp	between shoe base and glass	none
One part number ** CRL LTLSSO taper locking clamp	between shoe base and glass	none
One part number ** CRL LTLGSC taper locking clamp	between shoe base and glass	none
One part number ** CRL LTLSSC taper locking clamp	between shoe base and glass	none



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Project Number: 09-1892


Sample Installation

The shoe base was fastened to the steel weld block part number **BSWB5 with a single row of number 1/2-13 by 3/4" long stainless steel socket head cap screws located 6 1/2" from each end and remaining on 12" center, the weld block was welded to a steel test fixture.


Sample: A-3	Temperature: 10	2°F	Barometric Reading: 30.36 inches Hg
Title	of Test	Pressure	Notes
1/2 Structural L	oad Test Positive Load	60.0 psf	20 EUROS /
	111111	Results	Passed

Sample: A-3	Temperature: 102	°F	Barometric Reading: 30.36 inches Hg
Title o	f Test	Pressure	Notes
1/2 Structural L	oad Test Negative Load	60.0 psf	1 / / 22/22/2
	V / / / / / / / / / / / / / / / / / / /	Results	Passed

Sample: A-3	Temperature:	102°F	Barometric Reading:	30.36 inches Hg
Title o	f Test	Pressure	Notes	
Design Load Te	st Positive Load	60.0 psf	1111111	



Reading#	Deflection	Permanent Set	Results	Add. Info	
1	2.561"	N/A	Passed		
2	0.012"	0.005"	Passed		
Actual N	lovement	Actual Set	Recovery	Add. Info	
1) 2.561"		none	100%		



Cert. No: TST1657 Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020


File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: A-	3 Temperatu	re: 102°F	Baro	metric Reading:	30.36 inches Hg
Ti	tle of Test	Press	sure Not	es	
Design Load	d Test Negative Loa	d 60.0 psf			
		Wille.	•		
		111/17/1	②		
Reading#	Deflection	Permanent Set	Results	Add. Info	
Reading#	Deflection 2.664"	Permanent Set N/A		Add. Info	
Reading#		100 100 100 100 100 100 100 100 100 100	Results	Add. Info	
1	2.664" 0.019"	N/A	Results Passed	Add. Info	

Sample: A-3	Temperature	: 102°F	Baron	etric Reading:	30.36 inches Hg	
Titl	e of Test	Pressur	re Notes			
Uniform Strue	ctural Test Positive l	Load 120.0 psf	11/1/1/			
Recovery: 10	0%		•			
		1 1	1 1			
			2			
			9			
Reading#	Deflection	Permanent Set	Results	Add. Info		
Reading#	Deflection 3.215"			Add. Info		



Report Date: 6/22/2010


Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: A-3	Temperature	:: 102°F	Baro	metric Reading: 30.36 inc	thes Hg
Title	e of Test	Pressu			- 0
Uniform Struc	tural Test Negative	Load 120.0 psf			
Recovery: 100	0%	Wite.	•		
			②		
Reading#	Deflection				
Reading#	Deflection	Permanent Set	Results	Add. Info	
Reading#	Deflection 3.437*			Add. Info	




Cert. No: TST1657 Report Date: 6/22/2010 Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT


Sample: A-3	Temperature:	75.2°F	Barometric Reading:	30.24inches Hg
Title of Test		Notes		
Large Missile In	npact Test	Large missile o	cannon #105	
Missile Weigh	it	Missile		
9.0 pounds		2" by 4" by 92	" long	



Impact	Speed	Results	Add. Info
1	50.3 ft/sec	Passed	2000 / Williams 1997
2	50.9 ft/sec	Passed	V / 7948 / VIEWS / REMSA /
3	51.0 ft/sec	Passed	/ 1888 / / / / / / / / / / / / / / / / /
4	50.8 ft/sec	Passed	1 627 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
5	50.4 ft/sec	Passed	
6	50.6 ft/sec	Passed	() () () ()

Sample: A-3	Temperature:	75.2°F	Barometric Reading: 30.24 inches Hg		
Title o	f Test	Results			
ANSIZ97.1		Passed	Passed		
1) Center of lef	t lite				
2) Center of ce	nter lite				
3) Center of rig	ht lite				

DESCRIPTION OF SAMPLE				
Model Designation: Dry Glazed Concrete Mount Aluminum Glass Glazed Railing System				
Overall Size:	15' - 1" (181") by 4' - 0" (48") high			
Sample B-1				



Cert. No: TST1657 Report Date: 6/22/2010 Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143


OFFICIAL TEST REPORT

MATERIAL CHARACTERISTICS						
Members	Material**	Part Number**	Joint Type			
Cap Hand Rail:	stainless steel	** Part Number CRL LR20	none			
Glass Shoe Base:	6063-T52	** Part Number L25S10D	none			

4	Glazing	10 / Miles 1997 / / /	
Glazing Location	Glazing Material	Glazing Compound	Compound Color
All three lites of splass #25.5 mm nominal laminated glass composed of *(2) 1/2" Temp Glass		None	None
Interlaying Film: 0.06	0" **DuPont SentryGlas Plus	Laminator: Oldcastle	
Gla sha	mple is pocket glazed system using a azed at bottom with CRL taper lock caped setting block and taper locking cated 6" from each end and remaining	lamping system which consis lamps between glass and alu	ts of a " L "
Daylight Opening	60" by 36" high		

	Product Markings	
None		

	Additional Informatio	Additional Information					
Quantity and Type	Location	Method of Attachment					
One part number **CRL LR21PV vinyl gasket	between glass and hand rail	none					
One part number **CRL LTLSB setting block	between shoe base and glass	none					
One part number ** CRL LTLGSO taper locking clamp	between shoe base and glass	none					
One part number ** CRL LTLSSO taper locking clamp	between shoe base and glass	none					
One part number ** CRL LTLGSC taper locking clamp	between shoe base and glass	none					
One part number ** CRL LTLSSC taper locking clamp	between shoe base and glass	none					



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Project Number: 09-1892


Sample Installation

The shoe base was fastened to concrete test slab with a single row of No. 1/2 by 3 3/4" Hilti expansion bolt located 6" from each end and remainder on 6" centers.


Sample: B-3	-3 Temperature: 76.2°F		Barometric Reading: 30.31 inches Hg		
Title o	of Test	Pressure	Notes		
1/2 Structural Load Test Positive Load		60.0 psf			
	11/1/	Results	Passed		

Sample: B-3	Temperature: 76.	2°F	Barometric Reading: 30.31 inches Hg		
Title o	f Test	Pressure	Notes		
1/2 Structural Load Test Negative Load		60.0 psf	(MESSER / / / / / / / / / / / / / / / / / / /		
	1 / / / / / / / / / / / / / / / / / / /	Results	Passed		

Sample: B-3 Temperature: 76.4°F		76.4°F	Barometric Reading: 30.32 inches Hg
Title o	f Test	Pressure	Notes
Design Load Te	st Positive Load	60.0 psf	S2 / / 595553554* / /



Reading#	Deflection	Permanent Set	Results	Add. Info	
1	4.250"	N/A	Passed		
2	0.337"	none	Passed		
Actual N	lovement	Actual Set	Recovery	Add. Info	
1) 4.250"		none	100%		



4.355"

0.365"

0.377"

Movement

1) 4.355"

N/A

0.002"

Set

none

none

Cert. No: TST1657

Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Project Number: 09-1892

Title of Test Pressure Notes Design Load Test Negative Load 60.0 psf	Sample: B-3	Temperature:	76.4°F	Baro	metric Reading:	30.32 inches Hg	
	Title of Test Pressure		sure No	Notes			
	Design Load To	est Negative Load	60.0 psf				
				②			

Passed

Passed


100%

Recovery

Add. Info

Sample: B-3	ample: B-3 Temperature: 76.4°F		Baro	Barometric Reading: 30.32 inches Hg Notes	
Title of Test		Pressu	re Notes		
Uniform Struc	tural Test Positive I	oad 120.0 psf			
			(a)		
Reading#	Deflection	Permanent Set	Results	Add. Info	
1	4.365"	N/A	Passed		

Passed



Report Date: 6/22/2010

Completion Date: 5/19/2010


Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: B-3	Temperature	:: 76.4°F	Baron	metric Reading: 30.32 inches Hg		
Titl	Title of Test Pressure			Notes		
Uniform Strue	tural Test Negative	Load 120.0 psf				
Recovery: 10	1%	11/1/11				
		111/11/	17/30			
		7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	A			
			2	1		
			2	1		
			②			
			②			
Reading#	Deflection			l Add Info		
Reading#	Deflection	Permanent Set	Results	Add. Info		
Reading#	Deflection 4.442" 0.401"			Add. Info		



Cert. No: TST1657 Report Date: 6/22/2010 Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634


Lab. Number: 6143

OFFICIAL TEST REPORT

	Temperature:	76.8°F	Barometric Reading: 30.25inches Hg
Title of Test		Notes	
Large Missile In	npact Test		
Missile Weigh	it	Missile	
9.0 pounds		2" by 4" by	92" long
		(3)	
Impact	Speed	Results	Add. Info
Impact I	Speed 50.6 ft/sec	Results Passed	Add. Info
Impact I	1 15 W 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Add. Info
1	50.6 ft/sec	Passed	Add. Info
2	50.6 ft/sec 50.4 ft/sec	Passed Passed	Add. Info
2	50.6 ft/sec 50.4 ft/sec 50.4 ft/sec	Passed Passed Passed	Add. Info

Sample: B-3	Temperature: 76.8°F		Barometric Reading: 30.25 inches Hg		
Title of Test Results		Results			
ANSIZ97.1		Passed			
1) Center of lef	t lite				
2) Center of ce	nter lite				
3) Center of rig	ht lite				

DESCRIPTION OF SAMPLE				
Model Designation:	Dry Glazed Fascia Mount To Steel Aluminum Glass Glazed Railing System			
Overall Size:	15' - 1" (181") by 3' - 6" (42") high			
Sample C-1				



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143


OFFICIAL TEST REPORT

	MATERIAL CHARACTER	USTICS	
Members	Material**	Part Number**	Joint Type
Cap Hand Rail:	stainless steel	** Part Number CRL LR20	none
Glass Shoe Base:	6063-T52	** Part Number L25S10D	none

9	Glazing	Sec. 1 (1)	79	
Glazing Location	Glazing Material	Glazing Compound	Compound Color	
All three lites of glass emposed of *(2) Temp Glass		None	None	
Interlaying Film: 0.06	0" **DuPont SentryGlas Plus	Laminator: Oldcastle		
GI: sha	mple is pocket glazed system using a azed at bottom with CRL taper lock cl aped setting block and taper locking c eated 6" from each end and remaining	lamping system which consis lamps between glass and alu	ts of a " L "	
Daylight Opening	60" by 41 3/16" high	11/1/1/1/		

	Product Markings
None	

Additional Information				
Quantity and Type	Location	Method of Attachment		
One part number **CRL LR21PV vinyl gasket	between glass and hand rail	none		
One part number **CRL LTLSB setting block	between shoe base and glass	none		
One part number ** CRL LTLGSO taper locking clamp	between shoe base and glass	none		
One part number ** CRL LTLSSO taper locking clamp	between shoe base and glass	none		
One part number ** CRL LTLGSC taper locking clamp	between shoe base and glass	none		
One part number ** CRL LTLSSC taper locking clamp	between shoe base and glass	none		



Report Date: 6/22/2010

Completion Date: 5/19/2010

Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT


Project Number: 09-1892

Sample Installation


The shoe base was fastened to the steel tube with a single row of number 1/2-13 by 3/4" long stainless steel socket head cap screws located 6 1/2" from each end and remaining on 12" center, the steel tube was welded to a steel test fixture.

Sample: C-3	Temperature: 69.0°F		Barometric Reading: 30.25 inches Hg	
Title o	of Test	Pressure	Notes	
1/2 Structural L	oad Test Positive Load	60.0 psf	DE SEERS NO.	
	71111	Results	Passed	

Sample: C-3	Temperature:	69.0°F	Barometric Reading: 30.25 inches Hg	
Title o	f Test	Pressure	Notes	
Design Load Tes	st Positive Load	60.0 psf	1 / 1 / (2000) / / / / /	



Reading#	Deflection	Permanent Set	Results	Add. Info	
1	1.719"	N/A	Passed		
2	0.094"	0.005"	Passed		
Actual N	lovement	Actual Set	Recovery	Add. Info	
1) 1.719"		none	100%		



Cert. No: TST1657 Report Date: 6/22/2010 Completion Date: 5/19/2010 Expiration Date: 5/19/2020


File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: C-	3 Temperatur	re: 74.1°F	Baro	metric Reading:	30.30 inches Hg
Title of Test Pressure		sure Not	Notes		
Design Load	d Test Negative Load	60.0 psf			
			•		
			② L		
Reading#	Deflection	Permanent Set	Results	Add. Info	
Reading#	Deflection			Add. Info	
Reading#		Permanent Set		Add. Info	
Reading# 1 2 Moveme	1.885" 0.087"	Permanent Set		Add. Info	

Sample: C-3	Temperature	: 76.4°F	Barometric Reading: 30.32 inches Hg
Tit	le of Test	Pressu	re Notes
Uniform Stru	ctural Test Positive	Load 120.0 psf	
Recovery: 10	0%		•
Reading#	Deflection	Permanent Set	Results Add. Info
Reading#	Deflection 2.125"	Permanent Set	Results Add. Info Passed



Report Date: 6/22/2010


Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: C-3	Temperature	: 74.1°F	Barometric Reading: 30.30 inches Hg
Title	Title of Test Pressure Notes		
Uniform Struc	tural Test Negative	Load 120.0 psf	
Recovery: 100	9%		•
			2 - b
Reading#	Deflection	Permanent Set	Results Add. Info
1	2.105"	N/A	Passed



Cert. No: TST1657 Report Date: 6/22/2010 Completion Date: 5/19/2010

Expiration Date: 5/19/2020

File Number: 09-634


Lab. Number: 6143

Sample: C-3	Temperature:	79.7°F	Barometric Reading: 30.24inche
Title of Test		Notes	
Large Missile In	npact Test		
Missile Weigh	it	Missile	
9.25 pounds		2" by 4"	* by 92" long
		(2	3
Impact	I Sneed		
Impact	Speed	Results	Add. Info
Impact I	Speed 50.6 ft/sec 49.7 ft/sec		

ample C 1	T	24.000	(())
6	50.3 ft/sec	Passed	
5	50.0 ft/sec	Passed	111111
4	50.6 ft/sec	Passed	
3	50.2 ft/sec	Passed	M / / / / / / /
2	49.7 ft/sec	Passed	H / 1889 / / / /
ı	50.6 ft/sec	Passed	A / 1985/888477
	The second secon		

Sample: C-3	Temperature:	75.2°F	Barometric Reading:	30.18 inches Hg
Title of Test Re		Title of Test Results		
ANSIZ97.1		Passed		
1) Center of lef	t lite			
2) Center of cer	nter lite			
3) Center of rig	ht lite			

DESCRIPTION OF SAMPLE		
Model Designation:	Dry Glazed Concrete Fascia Mount Aluminum Glass Glazed Railing System	
Overall Size:	15' - 1" (181") by 3' - 6" (42") high	
Sample D-1		



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143


OFFICIAL TEST REPORT

MATERIAL CHARACTERISTICS			
Members	Material**	Part Number**	Joint Type
Cap Hand Rail:	stainless steel	** Part Number CRL LR20	none
Glass Shoe Base:	6063-T52	** Part Number L56S10D	none

A	Glazing	rds, 1998/00/11 / 1/	
Glazing Location	Glazing Material	Glazing Compound	Compound Color
All three lites of glass	*25.5 mm nominal laminated glass composed of *(2) 1/2" Temp Glass	None	None
Interlaying Film: 0.06	0" **DuPont SentryGlas Plus	Laminator: Oldcastle	
GI	mple is pocket glazed system using a azed at bottom with CRL taper lock cl aped setting block and taper locking c cated 6" from each end and remaining	amping system which consis lamps between glass and alu	ts of a " L "
Daylight Opening	60" by 42" high	7///////	

	Product Markings	
None	111111111	

Additional Information			
Quantity and Type	Location	Method of Attachment	
One part number **CRL LR21PV vinyl gasket	between glass and hand rail	none	
One part number **CRL LTLSB setting block	between shoe base and glass	none	
One part number ** CRL LTLGSO taper locking clamp	between shoe base and glass	none	
One part number ** CRL LTLSSO taper locking clamp	between shoe base and glass	none	
One part number ** CRL LTLGSC taper locking clamp	between shoe base and glass	none	
One part number ** CRL LTLSSC taper locking clamp	between shoe base and glass	none	



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Project Number: 09-1892


Sample Installation

The shoe base was fastened to concrete test slab with a single row of No. 1/2 by 3 3/4" Hilti expansion bolt located 6 1/2" from each end and remainder on 6" centers.


Sample: D-3	Temperature: 71.6°F		Barometric Reading: 30.30 inches Hg	
Title of Test Pressure		Pressure	Notes	
1/2 Structural L	/2 Structural Load Test Positive Load 60.0 psf			
Results		Results	Passed	

Sample: D-3	Temperature: 79.	9°F	Barometric Reading: 30.30 inches Hg
Title o	f Test	Pressure	Notes
1/2 Structural L	oad Test Negative Load	60.0 psf	
		Results	Passed

Sample: D-3	Temperature:	71.6°F	Barometric Reading: 30.30 inches Hg
Title o	f Test	Pressure	Notes
Design Load Tes	st Positive Load	60.0 psf	



Reading#	Deflection	Permanent Set	Results	Add. Info	
1	1.627"	N/A	Passed		
2	0.009**	none	Passed		
Actual N	lovement	Actual Set	Recovery	Add. Info	
1) 1.627*		none	100 %		



Cert. No: TST1657 Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020


File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: D-	3 Temperate	re: 79.9°F	Baron	netric Reading:	30.30 inches Hg
Ti	tle of Test	Press	ure Not	es	
Design Load	d Test Negative Lo	ad 60.0 psf			
			11/7		
Reading#	Deflection	Permanent Set	Results	Add. Info	
Reading#	Deflection			Add. Info	
Reading#		Permanent Set	Results	Add. Info	
1	1.545" 0.051"	Permanent Set	Results Passed	Add. Info	

Sample: D-3	Temperature	: 71.6°F	Barometric Reading: 30.30 inches Hg
Title	of Test	Pressu	re Notes
Uniform Struc	tural Test Positive	Load 120.0 psf	
Recovery: 100)%	211111	91 1
		1000	
			2)
Reading#	Deflection	Permanent Set	Results Add. Info
	3.160"	N/A	Passed
,			



Report Date: 6/22/2010

Completion Date: 5/19/2010


Expiration Date: 5/19/2020

File Number: 09-634

Lab. Number: 6143

OFFICIAL TEST REPORT

Sample: D-3	Temperature	: 79.9°F	Baro	metric Reading: 30.30 inches Hg
Titl	e of Test	Pressu	re Notes	5
Uniform Struc	ctural Test Negative	Load 120.0 psf		
Recovery: 10	0%	Miller	•	
			2	P
Reading#	Deflection	Permanent Set	Results	Add. Info
Reading#	Deflection 3.161"			Add. Info



Report Date: 6/22/2010

Completion Date: 5/19/2010 Expiration Date: 5/19/2020

File Number: 09-634


Lab. Number: 6143

Sample: D-3 Temperature:	95.0°F	Barometric Reading: 30.21 inches
Title of Test	Notes	
Large Missile Impact Test		
Missile Weight	Missile	
9.25 pounds	2" by 4" by 92"	long
	0 0	

Impact	Speed	Results	Add. Info
I	50.4 ft/sec	Passed	/ 1000A / VARRESTER / 1
2	50.6 ft/sec	Passed	1 200 1 200 1 1 200 1
3	50.3 ft/sec	Passed	1 8888 1 1 1 1 1 1 1 1 1
4	50.3 ft/sec	Passed	1 63.13.13.13.13.
5	50.7 ft/sec	Passed	
6	49.8 ft/sec	Passed	

Sample: D-3	Temperature:	83.7°F	Barometric Reading: 30.39 inches Hg
Title o	f Test	Results	
ANSIZ97.1		Passed	
1) Center of lef	t lite		
2) Center of cer	nter lite		
3) Center of rig	ht lite		

Revision	Description	Author	Effective Date	
0	Initial Release	Mr. Manny Sanchez	6/22/2010	



Report Date: 6/22/2010

Completion Date: 5/19/2010

Expiration Date: 5/19/2020 File Number: 09-634

Lab. Number: 6143

Project Number: 09-1892

OFFICIAL TEST REPORT

Notes

- designates measurements by laboratory
- ** as per manufacturer

At conclusion of ASTM E330 test and ANSI Z-97 drop test, there was no apparent damage to concrete test slab, glass and fasteners. At the conclusion of ASTM E1996 large missile test, the glass did break but remained intact and no shear or opening which a 3" diameter solid sphere could pass freely through.

The test specimens were covered with a 6 mil plastic sheeting to seal from air leakage when load test were conducted, however this had no effect on the above test results.

Remarks

Representative samples of the test specimens and detailed drawings will be retained by Fenestration Testing Laboratory for a period of five years from the original test date, and test report for a period of ten years. Due to the code cycle change of four years, it is recommended that this report be evaluated during the lifespan of this document.

This product was tested and meets the requirement set forth by the Florida Building Code (2007) TAS 201 large missile and ASTM E330. Sample A-1, B-1, C-1 and D-1 don't meets Section 1620.2 of this code. This product was tested in accordance with ANSI Z-97.1 section 1618.4.6.3.

Testing was conducted as per instructions received from your company representative.

Witnessed by:

Mr. Jorge A. Causo, P.E.

Mr. Abe Armenteros, C.R. Laurence

FENESTRATION TESTING LABORATORY, INC.

Manny Panclez

Mr. Manny Sanchez


Chief Executive Officer

TEST (A3) M	TEST (A3) MATERIAL LIST 1-1/16" (25.52MM) GLASS	TES
CAT#	DISCRIPTION	9
L25S	1-1/16" (25.52MM) ALUMINUM BASE SHOE	125
LTL10	CRL TAPERLOC LAMINATED TAPER SET	5
SHCSM14X34	M14 HEX HEAD ANCHOR BOLT	SHC
LSWB21	1/2" TALL STEEL WELD BLOCK	LR2
LR20	2" DIA CAP RAIL FOR 3/4" GLASS	LR2
LR22PV	PROTECTIVE CAP RAIL VINYL INSERT	980
95CBL	SILICONE SEALANT (BLACK)	

TEST (C3) M	TEST (C3) MATERIAL LIST 1-1/16" (25.52MM) GLASS
CAT	DISCRIPTION
L25SF	1-1/16" (25.52MM) ALUMINUM BASE SHOE
LTL10	CRL TAPERLOC LAMINATED TAPER SET
SHCSM14X34	SHCSM14X34 M14 HEX HEAD ANCHOR BOLT
LR20	2" DIA CAP RAIL FOR 3/4" GLASS
LR22PV	PROTECTIVE CAP RAIL VINYL INSERT
95CBL	SILICONE SEALANT (BLACK)


CAT#	DISCRIPTION
1258	1-1/16* (25.52MM) ALUMINUM BASE SHOE
LTL10	CRL TAPERLOC LAMINATED TAPER SET
E8A335	M14 HILTI CONCRETE EXPANSION ANCHOR
LR20	2" DIA CAP RAIL FOR 3/4" GLASS
LR22PV	PROTECTIVE CAP RAIL VINYL INSERT
95CBL	SILICONE SEALANT (BLACK)

TEST (D3) A	TEST (D3) MATERIAL LIST 1-1/16" (25.52MM) GLASS
CAT#	DISCRIPTION
L25SF	1-1/16" (25.52MM) FASCIA ALUM BASE SHOE
LTL10	CRL TAPERLOC LAMINATED TAPER SET
EBA335	M14 HILTI CONCRETE EXPANSION ANCHOR
LR20	2" DIA CAP RAIL FOR 34" GLASS
LR22PV	PROTECTIVE CAP RAIL VINYL INSERT
95CBL	SILICONE SEALANT (BLACK)



- BASE SHOE

TYPICAL ELEVATION AT TEST A-3, B-3, C-3, & D-3



23

TEST C-3

#L25S10F FASCIA MNT BASE SHOE ATTACHED TO STEEL

TEST D-3

CRL 25.52mm LAMINATED GLASS RAIL SYSTEM CRL 25.52mm LAMINATED GLASS RAIL SYSTEM CRL 25.52mm LAMINATED GLASS RAIL SYSTEM
#L25510D SURFACE MINT BASE SHOE
#L25510D SURFACE MINT BASE SHOE
#L25510D SURFACE MINT BASE SHOE ATTACHED TO CONCRETE

TEST A-3

#L25S10D SURFACE MNT BASE SHOE ATTACHED TO STEEL WELD BLOCK

#L25S10D SURFACE MNT BASE SHOE ATTACHED TO CONCRETE TEST B-3



BUILDING CODE COMPLIANCE OFFICE (BCCO)
PRODUCT CONTROL DIVISION

MIAMI-DADE COUNTY, FLORIDA METRO-DADE FLAGLER BUILDING 140 WEST FLAGLER STREET, SUITE 1603 MIAMI, FLORIDA 33130-1563 (305) 375-2901 PAX (305) 372-6339 www.miamidade.gov/buldingcode

NOTICE OF ACCEPTANCE (NOA)

E.I. DuPont de Nemours & Co., Inc.

8480 DuPont Road

Washington, WV 26181

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed by Miami-Dade County Product Control Division and accepted by the Board of Rules and Appeals (BORA) to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Division (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. BORA reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Division that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building

Code, including the High Velocity Hurricane Zone.

DESCRIPTION: DuPont SentryGlas@ Plus

APPROVAL DOCUMENT: Drawing No.319.58, sheet 1 of 1, titled "DuPont Sentryglass® Plus Interlayer" dated 10/01/07, prepared by E.I. DuPont DeNemours & Co., Inc., signed and sealed by Allan A. Kozich, P.B., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Division.

MISSILE IMPACT RATING: None. This approval does not include an evaluation of structural performance of this component. Test reports and other required documents shall be submitted to Dade County Product Control; showing that the systems using this interlayer sheet will resist the loads according to Chapter 16 of the P.B.C., in order to issue a specific product approval for the system.

LABBLING: Laminated lites under this Product Approval shall be permanently marked in a corner of the glass with: "DCA-SGP", standing for "Miami-Dade County Approved - SentryGlas Plus", and the laminator's identification mark. These marks shall be applied by the individual laminator producing the finished laminated glass product containing the SentryGlas® Plus ionoplast interlayer.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Pailure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews and revises NOA # 06-1205.10 and consists of this page, evidence page E-1, as well as approval document mentioned above.

The submitted documentation was reviewed by Carlos M. Utrera, P.E.



12/1/07

NOA No: 07-1116.04 Expiration Date: January 14, 2012 Approval Date: January 3, 2008

NOTICE OF ACCEPTANCE: EVIDENCE PAGE

A. DRAWING

 Drawing No. 319.58, sheet 1 of 1, titled "DuPont Sentryglass® Plus", dated 10/01/07, prepared by E.I. DuPont DeNemours & Co., Inc., signed and sealed by Allan A. Kozich, P.E.

B. TEST REPORTS

	Laboratory Report	Test	Date	Signature
1.	3136116SAT-001	ASTM D 635	10/25/07	Chris Bowness, P.E.
2.	3111755SAT-002	ASTM D1929	01/02/07	Chris Bowness, P.E.
3.	3111755SAT-001	ASTM E 84	12/19/06	Chris Bowness, P.B.
4.	PR106246	ASTM G 26	06/26/07	Duc T. Nguyen, P.E.
5.	PR106246	ASTM D 790	06/26/07	Duc T. Nguyen, P.E.

C. CALCULATIONS

None

D. MATERIAL CERTIFICATIONS

None

E. QUALITY ASSURANCE

Miami Dade Building Code Compliance Office (BCCO)

F. STATEMENTS

- Letter of No Financial Interest by R. B. Fisher & Associates, Inc., issued on 12/12/98, signed and sealed by W. M. Meyers, PB.
- Letter of Code Compliance by R. B. Fisher & Associates, Inc., issued on 12/12/98, signed and sealed by W. M. Meyers, PE.
- Letter of No Financial Interest by C. A. Smith of B. I. DuPont DeNemours & Co., Inc., issued on 12/18/98, signed and notarized by C. A. Smith.
- Approved listing of SentryGlas® Plus laminators dated November 30, 2005, signed by Jeffrey D. Granato. (Evidence Submitted under NOA # 06-1205.10)


G. OTHERS

 No change letter issued by E.I. DuPont de Nemours & Co., Inc., dated 11/01/07, signed by C. Anthony Smith, Ph.D.

> Carlos M. Utrera, P.E. Product Control Examiner NOA No 07-1116.04

Expiration Date: January 14, 2012 Approval Date: January 3, 2008

DUPONT SENTRYGLAS®PLUS INTERLAYER



PRODUCT DESCRIPTION

MANUFACTURED BY: E.I. DUPONT DE NEMOURS & CO., INC. DESCRIPTION: A PLASTIC INTERLAYER MATERIAL WHICH IS FACTORY LAMINATED TO A MINIMUM OF TWO PIECES OF GLASS.

A TYPICAL GLAZING IS MADE OF THE FOLLOWING COMPONENTS: (MINIMUM THICKNESS INDICATED. MULTIPLE PLIES OF INTERLAYER TO BE USED AS NECESSARY).

A B C SECTION

Α	-	1/8" (3.0 mm) Annealed Glass			
В	-	0.030" (0.76 mm) DuPont SentryGlas®Plus Interlayer			
С		1/8" (3.0 mm) Annealed Glass			

MATERIAL CHARACTERISTICS SentryGlas®Plus Interlayer

Designation	Properties		
Flame Spread Index	35		
Smoke Developed Index	250		
Flash Ignition Temperature ASTM D1929		788 F	
Self Ignition Temperature	806 F		
Average Extent of Burning [1]	0 cm/mln.; Class C1		
Average Extent of Burning [2] ASTM D635 Average Modulus of Rupture ASTM D790		0 cm/mln.; Class C1	
		Weathering*	
*WEATHERING PER SEC	Before	After	
THE FLORIDA BUILD	5,415 psi	5,366 psl	

NOTES:

- [1] 30 mil (0.76mm) thickness DuPont SentryGlas®Plus Interlayer Sample
- [2] 120 mil (3.3mm) thickness DuPont SentryGlas@Plus Interlayer Sample
- [3] DuPont SentryGlas@Plus Interlayer By Itself Does Not Comply With The Florida Building Code

THIS IS A COMPONENT APPROVAL AND DOES NOT INCLUDE AN EVALUATION OF STRUCTURAL PERFORMANCE OF THIS COMPONENT. SYSTEMS INCORPORATING THIS COMPONENT SHALL APPLY FOR A PRODUCT APPROVAL TO THIS OFFICE AND SHALL SUBMIT REPORTS AND OTHER REQUIRED DOCUMENTS SHOWING THAT THE SYSTEM USING THIS COMPONENT WILL RESIST THE LOADS ACCORDING TO CHAPTER 16 OF THE FLORIDA BUILDING CODE.

07-116 04 NOV 0 5 2007

DuPont SentryGlas® Plus Interlayer

E.I. DuPont de Nemours & Co., Inc. 8480 DuPont Road

Washington, West Virginia 26181

Phone: 304-863-2182 Dwg. # 319.58 Sheet 1 of 1

Drawing Date: 10/1/07 Allan A. Kozich, PE Registration # 16864



Fenestration Testing Laboratory, Inc.

8148 N.W. 74th Avenue Medley, FL 33166 Phone: 305/885/3328 Fax: 305/885/3329 e-mail: ftldade@aol.com www.ftl-inc.com

6/28/10

RE: Letter Certifying Independence

Client: C.R. Laurence C.O. Inc.

Address: 2503 E. Vemon Avenue Los Angeles, California 90058-1897

Model Designation: Weld Block Dry Glazed Concrete Mount Aluminum Glass

Glazed Railing System

Laboratory Number: 6143

To whom it may concern:

Fenestration Testing Laboratory certifies the following:

- Fenestration Testing Laboratory, nor it's company representatives, have any financial interest in the above referenced company
- Fenestration Testing Laboratory, nor it's company representatives, have any controlling interest in the above referenced company
- The above referenced company is not affiliated to Fenestration Testing Laboratory, nor it's company representatives

If you have any questions, please do not hesitate to contact us at (305) 885-3328.

Sincerely,

Fenestration Testing Laboratory, Inc.

Wannyland

Manny Sanchez

Chief Executive Officer