

DALLAS LABORATORIES, INC.

CONSULTANTS AND TECHNOLOGISTS
ANALYTICAL AND RESEARCH CHEMISTS —
CHEMICAL ENGINEERS — PETROLEUM ENGINEERS

MEMBERS

AMERICAN INSTITUTE OF CHEMICAL ENGINEERS
NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS
TEXAS SOCIETY OF PROFESSIONAL ENGINEERS
ASM INTERNATIONAL
SOCIETY OF PETROLEUM ENGINEERS OF AIMEP. O. BOX 152837
1323 WALL ST.

DALLAS, TEXAS 75315

MEMBERS

AMERICAN CHEMICAL SOCIETY
AMERICAN SOCIETY FOR TESTING MATERIAL
AMERICAN NATIONAL STANDARDS INSTITUTE
AMERICAN SOCIETY FOR QUALITY CONTROLSubmitted By: U.S. Aluminum Corp. - Texas
200 Singleton Drive
Waxahachie, TX 75165Date: November 13, 1995
(Reissued: May 21, 1998)

Attn: Jeff Lockenour

Report No. 23184RRR

REPORTSUBJECT: Performance testing in accordance with ASTM E 283-91 (Air Infiltration), ASTM E 331-93 (Water Resistance), ASTM E 330-90 (Uniform Load Deflection) and ASTM E 330-90 (Uniform Load Structural).DESCRIPTION OF UNIT TESTEDType: Aluminum StorefrontSeries: "BG" SystemOverall Size: 7'11-1/4" x 7'7-1/4" (2.42 m x 2.318 m)Configuration: O.O
O.OGlass: Sealed insulating glass: 2 pcs 1/4" (6.35 mm) tempered, 1/2" (12.70 mm) air spacer, 1" (25.4 mm) overall thickness.Glazing: One row of NP255 gasket at exterior face of each fixed lite, full perimeter. Silicone spacer (SP455) at interior face of all vertical member of each fixed lite and vinyl gasket (NP225) at interior face of all horizontal member of each fixed lite. Vertical butt joint between the two pairs of fixed lite is sealed with silicone and SP455 spacers sealed with silicone.Weep Arrangement: Two 5/16" (7.94 mm) dia. weepholes in bottom of each lower fixed lite sill and one 1/4" (6.35 mm) dia. weephole at center intermediate horizontal member (total of 5 weeps in mock-up).Sealant: Exterior joint between (BG569) jamb and (BG560) snap-in filler are sealed full length with sealant. End dams at each end of intermediate horizontal members are sealed at perimeter.Other Features: Frame members are thermally broken. Horizontal intermediate member secured by shear block at each end. Shear blocks are secured to jambs and vertical intermediate jamb by two (2) #8x1/2" (8 x 12.70 mm) screws.Date Testing Started: September 22, 1995Date Testing Completed: November 6, 1995


SUMMARY OF TEST RESULTS

<u>TITLE OF TEST</u>	<u>TEST METHOD</u>	<u>MEASURED</u>	<u>ALLOWED</u>
Air Infiltration @ 6.24 psf (30.46 kg/m ²)	ASTM E 283-91	0.04 CFM/Ft ² (0.019 liter/sec)	0.06 CFM/Ft ² (0.028 liter/sec)
Water Resistance @ 12.00 psf (58.58 kg/m ²)	ASTM E 331-93	No Leakage	No Leakage
Uniform Load Deflection	ASTM E 330-90		
- Exterior 20.0 psf (97.64 kg/m ²)		0.283" (7.188 mm)	0.497" (12.62 mm)
- Interior 20.0 psf (97.64 kg/m ²)		0.234" (5.944 mm)	0.497" (12.62 mm)
Uniform Load Structural	ASTM E 330-90		
- Exterior		30.0 psf * (146.44 kg/m ²)	30.0 psf * (146.44 kg/m ²)
- Interior		30.0 psf * (146.44 kg/m ²)	30.0 psf * (146.44 kg/m ²)
- Permanent Set		Negligible	0.365" (9.271 mm)

* No glass breakage, permanent deformation, or other damage causing the unit to be inoperable.

The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specifications.

DALLAS LABORATORIES, INC.
TESTING LABORATORY



DIRECTOR, WINDOW & DOOR TESTING

WAW:df