TELEPHONE (AREA CODE 214)

565-0594 421-1400

ASM INTERNATIONAL

DALLAS LABORATORIES, INC.

CONSULTANTS AND TECHNOLOGISTS

ANALYTICAL AND RESEARCH CHEMISTS —

CHEMICAL ENGINEERS — PETROLEUM ENGINEERS

P. O. BOX 152837 1323 WALL ST.

DALLAS, TEXAS 75315

MEMBERS

CABLE ADDRESS "DALAF

AMERICAN CHEMICAL SOCIETY
AMERICAN SOCIETY FOR TESTING MATERIA
AMERICAN NATIONAL STANDARDS INSTITUAMERICAN SOCIETY FOR QUALITY CONTRC

Submitted By:

MEMBERS

NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS

AMERICAN INSTITUTE OF CHEMICAL ENGINEERS

TEXAS SOCIETY OF PROFESSIONAL ENGINEERS

SOCIETY OF PETROLEUM ENGINEERS OF AIME

United States Aluminum Corp.

200 Singleton Dr.

Waxahachie, TX 75165

Attn: Mr. Doug Ellerbrock

Date: April 5, 1994

(Reissued: May 9, 1994)

Report No. 20932-R

RECEIVED

MAY 17 1994

UNITED STATE LUMINION

## REPORT

<u>Subject:</u> Performance testing in accordance with ASTM E 283-91 (Air Infiltration), ASTM E 331-86 (Water Resistance) and ASTM E 330-90 (Uniform Load Deflection and Uniform Load Structural).

## PRODUCT DESCRIPTION

Product Type: Store-front

Series Model: FF450 Flush Front Exterior Glazed

Overall Size: 8'1/2" x 7'11-3/16"

Configuration:  $0 \cdot \frac{0}{0}$ 

Glass: 1/4" tempered.

Glazing: Exterior glazed using NP-225 gasket at interior and exterior perimeter of glass.

Weep Arrangement: 1-1/4"x3/16" weep slot, approx. 2-1/2" from each vertical member - two under each lite (total of 4).

Scalant: Silicone sealant and foam backer rod used at full exterior perimeter of main frame. Silicone sealant at interior and exterior of sub-sill #FF400 to sill #FF482 full span, at each corner of sub-sill #FF400 to wood test buck and aluminum angle end cap to sub-sill #FF400. Silicone sealant applied to head of sill anchor bolts and vertical joints of mullion at head and sill of main frame.

Other Features: Frame corner construction by two (2) #10x1" screws. Snap-in glazing strip #M-473 at frame top rail. 1/4" dia. lag bolts employed to attach frame to wood test buck - one 2" from each vertical member and one at mid-point between mullion and frame jambs on frame head and frame sill. Horizontal member attached to mull and frame jamb with four (4) 10x1" screws at each corner (total of 8).

Date Testing Started: March 16, 1994

Date Testing Completed: March 16, 1994

THE ANALYSES OF THE ABOVE SAMPLE OR SAMPLES DO NOT IMPLY AN ENDORSEMENT. THIS REPORT, OR ANY PART THEREOF MAY NOT BE REPRODUCED OR USED FOR ADVERTISING PURPOSES WITHOUT OUR EXPRESS WRITTEN CONSENT.

## PERFORMANCE TEST RESULTS

TITLE OF TEST	TEST METHOD	MEASURED	ALLOWED
Air Infiltration @ 1.57 psf	ASTM E 283-91	0.008 CFM/Ft <sup>2</sup>	0.06 CFM/Ft <sup>2</sup>
Air Infiltration @ 6.24 psf	ASTM E 283-91	0.02 CFM/Ft <sup>2</sup>	0.06 CFM/Ft <sup>2</sup>
Water Resistance @ 6.24 psf	ASTM E 331-86	No Leakage	No Leakage
Water Resistance @ 8.00 psf	ASTM E 331-86	No Leakage	No Leakage
Water Resistance @ 10.00 psf	ASTM E 331-86	No Leakage	No Leakage
Uniform Load Deflection	ASTM E 330-90		
- Exterior 30.0 psf - Interior 30.0 psf		0.218" 0.259"	0.546" 0.546"
Uniform Load Structural	ASTM E 330-90		
- Exterior		45.0 PSF *	45.0 PSF *
- Interior		45.0 PSF *	45.0 PSF *
- Permanent		Negligible	0.386"

<sup>\*</sup> No glass breakage, permanent deformation, or any other condition exists that caused any damage to the unit.

The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specifications.

DALLAS LABORATORIES, INC. TESTING LABORATORY

ALION

AW:td

DIRECTOR, WINDOW AND DOOR TESTING