

DALLAS LABORATORIES, INC.

CONSULTANTS AND TECHNOLOGISTS
ANALYTICAL AND RESEARCH CHEMISTS —

CHEMICAL ENGINEERS — PETROLEUM ENGINEERS

MEMBERS

AMERICAN INSTITUTE OF CHEMICAL ENGINEERS
NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS
TEXAS SOCIETY OF PROFESSIONAL ENGINEERS
ASM INTERNATIONAL
SOCIETY OF PETROLEUM ENGINEERS OF AIMEP. O. BOX 152837
1323 WALL ST.

DALLAS, TEXAS 75315

MEMBERS

AMERICAN CHEMICAL SOCIETY
AMERICAN SOCIETY FOR TESTING MATERIAL
AMERICAN NATIONAL STANDARDS INSTITUTE
AMERICAN SOCIETY FOR QUALITY CONTROLSubmitted By: United States Aluminum Corp.
200 Singleton Dr.
Waxahachie, TX 75165Date: April 15, 1994
Reissued: May 26, 1998

Attn: Mr. Doug Ellerbrock

Report No. 20992-R

REPORTSubject: Performance testing in accordance with ASTM E 283-91 (Air Infiltration), ASTM E 331-86 (Water Resistance) and ASTM E 330-90 (Uniform Load Deflection and Uniform Load Structural).PRODUCT DESCRIPTIONProduct Type: Store-frontSeries Model: FF451 Flush Front Interior GlazedOverall Size: 8'5/8" x 7'11-1/4" (2.454 m x 2.419 m)Configuration:

$$O * \frac{O}{O}$$

Glass: Two pieces 1/4" (6.35 mm) annealed, 1/2" (12.70 mm) air spacer, 1" (25.4 mm) overall thickness.Glazing: Interior glazed using NP-225 gasket at interior and exterior perimeter of glass.Weep Arrangement: 1-1/4"x3/16" (31.75 mm x 4.763 mm) weep slot, approx. 2-1/2" (63.5 mm) from each vertical member - two under each lite (total of 4).Sealant: Silicone sealant and foam backer rod used at full exterior perimeter of main frame. Silicone sealant at interior and exterior of sub-sill #FF400 to sill #FF582 full span, at each corner of sub-sill #FF400 to wood test buck and aluminum angle end cap to sub-sill #FF400. Silicone sealant applied to head of sill anchor bolts and vertical joints of mullion at head and sill of main frame.Other Features: Frame corner construction by two (2) #10x1" (10 x 25.4 mm) screws. Snap-in glazing strip #M-473 at frame top rail. 1/4" (6.35 mm) dia. lag bolts employed to attach frame to wood test buck - one 2" (50.8 mm) from each vertical member and one at mid-point between mullion and frame jambs on frame head and frame sill. Horizontal member attached to mull and frame jamb with four (4) 10x1" (10 x 25.4 mm) screws at each corner (total of 8).Date Testing Started: March 21, 1994Date Testing Completed: March 21, 1994


PERFORMANCE TEST RESULTS

<u>TITLE OF TEST</u>	<u>TEST METHOD</u>	<u>MEASURED</u>	<u>ALLOWED</u>
Air Infiltration @ 1.57 psf (7.664 kg/m ²)	ASTM E 283-91	0.01 CFM/Ft ² (0.005 liter/sec)	0.06 CFM/Ft ² (0.028 liter/sec)
Air Infiltration @ 6.24 psf (30.46 kg/m ²)	ASTM E 283-91	0.03 CFM/Ft ² (0.014 liter/sec)	0.06 CFM/Ft ² (0.028 liter/sec)
Water Resistance @ 6.24 psf (30.46 kg/m ²)	ASTM E 331-86	No Leakage	No Leakage
Water Resistance @ 8.00 psf (39.051 kg/m ²)	ASTM E 331-86	No Leakage	No Leakage
Water Resistance @ 10.00 psf (48.82 kg/m ²)	ASTM E 331-86	No Leakage	No Leakage
Uniform Load Deflection	ASTM E 330-90		
- Exterior 30.0 psf (146.44 kg/m ²)		0.439" (11.15 mm)	0.546" (13.87 mm)
- Interior 30.0 psf (146.44 kg/m ²)		0.414" (10.52 mm)	0.546" (13.87 mm)
Uniform Load Structural	ASTM E 330-90		
- Exterior		45.0 PSF * (219.66 kg/m ²)	45.0 PSF * (219.66 kg/m ²)
- Interior		45.0 PSF * (219.66 kg/m ²)	45.0 PSF * (219.66 kg/m ²)
- Permanent		Negligible	0.386" (9.804 mm)

* No glass breakage, permanent deformation, or any other condition exists that caused any damage to the unit.

The above results were secured by using the designated test methods and they indicate compliance with the performance requirements of the above referenced specifications.

DALLAS LABORATORIES, INC.
TESTING LABORATORY



DIRECTOR, WINDOW AND DOOR TESTING
Andy Wilson

AW:df